

**SPP-NTC-210527**

**SPP  
Notification to Construct**

October 17, 2019

Mr. John Knofczynski  
East River Electric Power Cooperative  
P.O. Box 227  
Madison, SD 57042

RE: Notification to Construct Approved Reliability Network Upgrades

Dear Mr. Knofczynski,

Pursuant to Section 3.3 of the Southwest Power Pool, Inc. ("SPP") Membership Agreement and Attachments O and Y of the SPP Open Access Transmission Tariff ("OATT"), SPP provides this Notification to Construct ("NTC") directing East River Electric Power Cooperative ("EREC"), as the Designated Transmission Owner, to construct the Network Upgrade(s).

On May 31, 2019, SPP concluded that the Network Upgrade(s) below are required on the EREC system to fulfill delivery point addition request(s) as detailed in the Delivery Point Network Study DPA-2018-January-821. On September 27, 2019, SPP received all executed Transmission Service Agreements associated with DPA-2018-January-821.

**New Network Upgrades**

**Project ID:** 81626  
**Project Name:** Multi - Wentworth 69 kV  
**Need Date for Project:** 8/1/2019  
**Estimated Cost for Project:** \$2,673,770

**Network Upgrade ID:** 122593  
**Network Upgrade Name:** Wentworth 69 kV Substation  
**Network Upgrade Description:** Build new Wentworth 69 kV Substation to replace existing motor-operated switch  
**Network Upgrade Owner:** EREC  
**MOPC Representative(s):** Mark Hoffman  
**TWG Representative:** John Knofczynski  
**Categorization:** Regional Reliability  
**Network Upgrade Specification:** All elements and conductor must have at least an emergency rating of 45 MVA.

**SPP-NTC-210527**

**Network Upgrade Justification:** DPA-2018-January-821  
**Estimated Cost for Network Upgrade (current day dollars):** \$2,073,095  
**Cost Allocation of the Network Upgrade:** Base Plan  
**Estimated Cost Source:** EREC  
**Date of Estimated Cost:** 7/10/2019

**Network Upgrade ID:** 122594  
**Network Upgrade Name:** Wentworth 69 kV Capacitor Bank  
**Network Upgrade Description:** New 7.2 MVAR capacitor bank at the new Wentworth 69 kV Substation  
**Network Upgrade Owner:** EREC  
**MOPC Representative(s):** Mark Hoffman  
**TWG Representative:** John Knofczynski  
**Categorization:** Regional Reliability  
**Network Upgrade Specification:** New 7.2 MVAR capacitor bank at the new Wentworth 69 kV Substation.  
**Network Upgrade Justification:** DPA-2018-January-821  
**Estimated Cost for Network Upgrade (current day dollars):** \$600,675  
**Cost Allocation of the Network Upgrade:** Base Plan  
**Estimated Cost Source:** EREC  
**Date of Estimated Cost:** 7/1/2019

**Commitment to Construct**

Please provide to SPP a written commitment to construct the Network Upgrade(s) within 90 days of the date of this NTC, in addition to providing a construction schedule and an updated  $\pm 20\%$  cost estimate, NTC Project Estimate, in the Standardized Cost Estimate Reporting Template for the Network Upgrade(s). Failure to provide a sufficient written commitment to construct as required by the SPP OATT could result in the Network Upgrade(s) being assigned to another entity.

**Mitigation Plan**

The Need Date represents the timing required for the Network Upgrade(s) to address the identified need. Your prompt attention is required for formulation and approval of any necessary mitigation plans for the Network Upgrade(s) included in the Network Upgrade(s) if the Need Date is not feasible. Additionally, if it is anticipated that the completion of any Network Upgrade will be delayed past the Need Date, SPP requires a mitigation plan be filed within 60 days of the determination of expected delays.

**Notification of Commercial Operation**

Please submit a notification of commercial operation for each listed Network Upgrade to SPP as

**SPP-NTC-210527**

soon as the Network Upgrade is complete and in-service. Please provide SPP with the actual costs of these Network Upgrades as soon as possible after completion of construction. This will facilitate the timely billing by SPP based on actual costs.


**Notification of Progress**

On an ongoing basis, please keep SPP advised of any inability on EREC's part to complete the approved Network Upgrade(s). For project tracking, SPP requires EREC to submit status updates of the Network Upgrade(s) quarterly in conjunction with the SPP Board of Directors meetings. However, EREC shall also advise SPP of any inability to comply with the Project Schedule as soon as the inability becomes apparent.

All terms and conditions of the SPP OATT and the SPP Membership Agreement shall apply to this Project, and nothing in this NTC shall vary such terms and conditions.

Don't hesitate to contact me if you have questions or comments regarding these instructions. Thank you for the important role that you play in maintaining the reliability of our electric grid.

Sincerely,

A handwritten signature in black ink that reads "Lanny Nickell".

Lanny Nickell

Vice President, Engineering

Phone: (501) 614-3232 • Fax: (501) 482-2022 • [lnickell@spp.org](mailto:lnickell@spp.org)

cc: Carl Monroe - SPP  
Antoine Lucas - SPP  
Jay Caspary - SPP  
James Edwards - EREC